



FICHE PRODUIT

Container mobile photovoltaïque 2-88 kWc

- Mobile
- Production silencieuse
- Montage rapide
- Maintenance simple

Caractéristiques techniques

Référence	
Puissance totale	2 à 88 kWc par container
Puissance par module (4 panneaux)	2 kWc
Nombre de modules	Variable (4 panneaux par module; 44 modules par container)
Temps de déploiement	10 minutes par module
Mode de déchargement	Grue; Camion grue; Chariot élévateur
Dimensions container (L×l×h)	6060×2440×2590 mm
Dimensions déployé (L×l×h)	Variable
Poids container vide	3500 kg
Poids pour 1 module (4panneaux)	190 kg



PRODUCT SHEET

Mobile Photovoltaic Container 2-88 kWp

- Mobile
- Quick assembly
- Silent operation
- Simple maintenance

Technical Specifications

Designation	
Total power	2 to 88 kWp per container
Power per module (4 panels)	2 kWp
Number of modules	Variable (4 panels per module; 44 modules per container)
Deployment time	10 minutes per module
Unloading method	Crane, Crane truck, Forklift
Container dimensions (L×I×h)	6060×2440×2590 mm
Deployed dimensions (L×I×h)	Variable
Empty container weight	3500 kg
Weight per module (4 panels)	190 kg